Managing Energy & Water Use at NERSC: Multidisciplinary Teamwork



Norman Bourassa Building Infrastructure Group HPC User Fal Forum - Sept. 6 & 7, 2023

Suzy's Guiding Questions

- Brief background about your center
- Define sustainability for your HPC center
- Do you have Sustainability Goals, if yes then
- Sustainability Goal hurdles
- Utility provider challenges
- Any HPC Application Code power efficiency work





Background: Shyh Wang Hall - Building 59



3








Office of Science

Background: Building 59 Section View



- Four-Story 150,000 GSF (13,935 M²)
 - Two 20k sf office floors, 300 offices
 - 28k sf HPC floor
 - 21.5 MW HPC Electrical Service
 - Current peak demand ~6 MW (Cori Retired)
- Energy Efficient
 - Year-round compressor-free air and water cooling
 - LEED Gold Rated Building
 - High resolution monitoring (OMNI system)
 - TTM PUE 1.05
- Room Air & Cooling Water
 - ~70% annual hours, single pass air
 - Full year, wet cooling towers provide 75°F (24°C) or colder Cooling Water (CW) for HPC loads








Office of

Science

Background: Trailing 12-Month (TTM) PUE NERSC PUE Dashboard (Jul 2023)

LBNL Energy Management Power Usage Effectiveness (PUE) Target < 1.10








Background: HPC Average Power History

6

Perlmutter: 3x Cori Flops, ~4.5 MW, ~50% MUS *







Edison: ~2 MW , 70% MUS (Retired 2018)

* Machine Unit Specification: Vendor provided peak power rating







Office of Science

Define Sustainability: Three Guiding Categories

- Compute Job & Application QA/QC
 - A failed Job is pure energy waste
 - Opportunities:
 - Job code "Tuned Approximation" for the science need
 - Typically 10% of active Jobs, responsible for 70% of power demand
- Site Specific Facility Design
 - Dissipate waste heat directly to outside environment or other end-uses
 - Avoid vapor-compression based cooling systems
- High Resolution Instrumentation for Operational Data Analytics (ODA)
 - Supporting all operational activities
 - Core tool for Ongoing Commissioning (OCx) of Building 59 systems





Sustainability Goals: NERSC Dominates Campus Energy


At ~35% of campus energy demand, NERSC is the Significant Energy User (SEU) in the LBNL Energy & Water Management Program

LBNL Receives DOE's 50001 Ready & ISO 50001



Photo Credit: LBHL. Styly Wang Hail, home of NERSC, the Lab's high performance computing center.

After nearly three years of development and implementation, Lawrence Beckeley National Laboratory (LBNL) received DOE's 50001 Ready recognition in June 2020, and was subsequently ISO 50001 certified in September 2020 with zero non-conformitles. <u>ISO 50001</u> is an international standard for managing and improving energy management and DOE's 50001 Ready Program is a free, self-guided approach based on the principles of the ISO guidance. LBNL pursued 50001 as a way to ensure both its energy and water management activities and efficiency savings were strategic, effective, and persistent.






8







Sustainability Goals: NERSC OMNI Data Infrastructure










Sustainability Goals: Inter-Division Collaboration



Bringing Science Solutions to the World



Utility Providers: DOE Lab Power Consortium


- A collaboration between three divisions of the U.S. Department of Energy (DOE):
 - Western Area Power Administration (WAPA)
 - Office of Science, Berkeley Site Office (BSO)
 - National Nuclear Security Administration (NNSA)
- Made possible by the federal government's investment in hydropower and transmission in California's Central Valley region
- An important component of advancing science by helping to keep research costs lower







Utility Providers: CA DOE Lab Locations & Interconnections









Office of

Science

App Power Codes: Jobs & Application Code Energy Efficiency



HPC EE studies at NERSC

- Detailed Job & App power profiling
- CPU vs GPU energy studies *
- Frequency tuning & energy-tosolution optimization

* Paper: VASP Performance on HPE Cray EX Based on NVIDIA A100 GPUs and AMD Milan CPUs, Zhengji Zhao (NERSC) et al, 2023.







Office of

Science



Thank You

Norman Bourassa, njbourassa@lbl.gov Energy & Water Performance Engineer NERSC - Building Infrastructure Group

Perlmutter (N-9) System




- Phase 1 delivered December 2021 to January 2022
 - 12 GPU cabinets (3 CDUs)
- Phase 2 delivered March 2022 to May 2022
 - 12 CPU cabinets (4 CDUs)
 - Development system rack + CDU
 - (Sandbox) Alvarez system rack + CDU
- Infrastructure in place to support another 9 racks and 2 CDUs
 - Expansion and POD systems installed (4 GPU cabinets + 2 CDUs)





NERSC - Mechanical Level










Office of Science

NERSC - Computer Level











Office of Science

ODA SkySpark - Cooling Tower Staging Data

